



**Secretariat**

**Distr.  
GENERAL**

**ST/SG/AC.10/C.4/2002/16/Add.9  
23 October 2002**

**ENGLISH  
Original: ENGLISH and FRENCH**

---

**COMMITTEE OF EXPERTS ON THE TRANSPORT OF  
DANGEROUS GOODS AND ON THE GLOBALLY  
HARMONIZED SYSTEM OF CLASSIFICATION  
AND LABELLING OF CHEMICALS**

**Sub-Committee of Experts on the  
Globally Harmonized System of Classification  
and Labelling of Chemicals  
(Fourth session, 9-11 December 2002  
agenda item 2)**

**GLOBALLY HARMONIZED SYSTEM OF CLASSIFICATION  
AND LABELLING OF CHEMICALS (GHS)**

**Submitted by the GHS Editorial Group**

**Annex 6**

**EXAMPLES OF ARRANGEMENTS OF THE GHS LABEL ELEMENTS**

## Annex 6



**Examples of arrangements  
of the GHS label elements**

**A6.1 Example 1**



The product is a liquid substance:

- classified under GHS as skin corrosive category 1B and flammable liquid category 3.
- UN Model Regulations on the Transport of Dangerous Goods classification is corrosive liquid, flammable, N.O.S., - UN 2920.



**A6.1.1 Label for large receptacle (200 litre drum) for transport, emergency response and workplace audiences**

UN 2920	<b>2-methyl tetramethylenexxxx</b>
Corrosive liquid, flammable, N.O.S.	<b>Danger</b>
(2-methyl tetramethylenexxxx)	Causes severe skin burns and serious eye damage Highly flammable liquid and vapour Avoid contact with skin and eyes Keep away from heat and ignition sources
 	
<b>First aid:</b>	
For skin contact, remove contaminated clothing and wash affected area thoroughly with water. If irritation develops, seek medical attention.	
For eye contact, immediately flush eyes with flowing water for at least 15 minutes and seek medical attention.	
GHS Example Company, Akron, NWT, Canada.	Telephone (888) 888-8888

**A6.1.2** *Label for small workplace receptacle (10 litre) packaged inside an outer transport packaging – for workplace audience*

<b>2-methyl tetramethylenexxxx</b>	
	
<b>Danger</b> Causes severe skin burns and serious eye damage Highly flammable liquid and vapour Avoid contact with skin and eyes Keep away from heat and ignition sources	
<b>First aid:</b> For skin contact, remove contaminated clothing and wash affected area thoroughly with water. If irritation develops, seek medical attention. For eye contact, immediately flush eyes with flowing water for at least 15 minutes and seek medical attention.	
GHS Example Company, Akron, NWT, Canada	Telephone (888) 888-8888

**A6.1.3** *Un transport markings and labels for the outer packaging of a “combined” transport packaging containing receptacles – for transport and emergency response audiences.*  
*Note: Only the UN transport markings and labels are required for such outer packagings.*



<b>UN 2920</b>	
<b>Corrosive liquid, flammable, N.O.S.</b> <b>(2-methyl tetramethylenexxxx)</b>	
	

**A6.2 Example 2**

The product is a liquid mixture:


- classified under GHS as toxic to reproduction, category 1B and flammable liquid, category 3.
- UN Model Regulations on the Transport of Dangerous Goods classification is flammable liquid - UN 1263.

**A6.2.1 Label for large receptacle (200 litre drum) for transport, emergency response and workplace audiences**

<b>ZZZ Red Paint</b>	
	
<b>UN 1263</b> <b>Paint</b>	<b>Danger</b>
	<p>May damage fertility or the unborn child          Highly flammable liquid and vapour          ** Contains lead pigments and cellosolve acetate          Keep away from heat and ignition sources          Keep away from food and drink          Avoid contact with skin and eyes and inhalation of vapour          Wash hands thoroughly after use and before eating</p>
<p><b>First aid:</b>          For skin contact, remove contaminated clothing and wash affected area thoroughly with water. If irritation develops, seek medical attention.          For eye contact, immediately flush eyes with flowing water for at least 15 minutes and seek medical attention.</p>	
<p>GHS Example plc, Leeds, England. Telephone 44 999 999 9999</p>	

\*\* Note: competent authorities may choose to not require disclosure of ingredient identities on the label of products intended for workplace use only – See Part I, par. 1.4.10.5.1 (a) (iii).

**A6.2.2** *Label for small workplace receptacle (10 litre) packaged inside an outer transport packaging – for workplace audience*

<p style="text-align: center;"><b>ZZZ Red Paint</b></p> <p style="text-align: center;"></p> <p style="text-align: center;"><b>DANGER</b></p> <p style="text-align: center;">May damage fertility or the unborn child Highly flammable liquid and vapour ** Contains lead pigments and cellosolve acetate Keep away from heat and ignition sources Keep away from food and drink Avoid contact with skin and eyes and inhalation of vapour Wash hands thoroughly after use and before eating</p> <p><b>First aid:</b> For skin contact, remove contaminated clothing and wash affected area thoroughly with water. If irritation develops, seek medical attention. For eye contact, immediately flush eyes with flowing water for at least 15 minutes and seek medical attention.</p> <p style="text-align: center;">GHS Example plc, Leeds, England. Telephone 44 999 999 9999</p>
---

\*\* *NOTE: competent authorities may choose to not require disclosure of ingredient identities on the label of products intended for workplace use only.*

**A6.2.3** *Un transport markings and labels for the outer packaging of a “combined” transport packaging containing receptacles – for transport and emergency response audiences.*

*Note: Only the UN transport markings and labels are required for such outer packagings.*

