


The secretariat reproduces below the amendment proposals submitted by Belgium.

1. Amend article 1.07, para. 4 as follows

In addition, the stability of vessels carrying containers shall be checked before departure for the following cases:

- (a) for vessels with a beam of less than 9.5 m, loaded with more than one tier of containers;
- (b) for vessels with a beam of 9.5 m or more but less than 11 m, loaded with more than two tiers of containers;
- (c) for vessels with a beam of 11 m or more **but less than 15 m**, loaded with more than three tiers of containers or more than three widths;
- (d) for vessels with a beam of 15 m or more, loaded with more than three tiers of containers.

2. Replace the illustrations 3.E and 3.E1, section II (3) of annex 8



3. Replace the illustrations 3.F and 3.F1, section II (3) of annex 8

